
BE225-02




INSPECTION

1. INSPECT PASSENGER'S DOOR LOCK CONTROL SWITCH CONTINUITY


Switch position	Tester connection	Specified condition
LOCK	2 – 3	Continuity
OFF	-	No continuity
UNLOCK	1 – 2	Continuity

If continuity is not as specified, replace the switch.



2. INSPECT PASSENGER'S DOOR LOCK CONTROL IN-DICATOR LIGHT OPERATION


Connect the positive (+) lead from the battery to terminal 4 and the negative (-) lead to terminal 2, and check that the indicator light does not light up, replace the switch.



3. Driver's door (w/o door closer): INSPECT DOOR KEY LOCK AND UNLOCK SWITCH CONTINUITY

Switch position	Tester connection	Specified condition
LOCK	2 – 4	Continuity
OFF	-	No continuity
UNLOCK	2 – 3	Continuity

If continuity is not as specified, replace the switch.



4. Driver's door (w/o door closer): INSPECT DOOR UNLOCK DETECTION SWITCH CONTINUITY

Switch position	Tester connection	Specified condition
OFF (Door Lock set to LOCK)	-	No continuity
ON (Door Lock set to UNLOCK)	1 – 2	Continuity


If continuity is not as specified, replace the switch.


UNLOCK LOCK (d321) N 120704

5. Passenger's door (w/o door closer) : INSPECT DOOR UNLOCK DETECTION SWITCH CONTINUITY


Switch position	Tester connection	Specified condition
OFF (Door Lock set to LOCK)	-	No continuity
ON (Door Lock set to UNLOCK)	3 – 4	Continuity

If continuity is not as specified, replace the switch.





UNLOCK LOCK (4321) 120706



Rear LH door (w/o door closer): 6. INSPECT DOOR UNLOCK DETECTION SWITCH CON-**TINUITY**

Switch position	Tester connection	Specified condition
OFF (Door Lock set to LOCK)	-	No continuity
ON (Door Lock set to UNLOCK)	1 – 2	Continuity

If continuity is not as specified, replace the switch.

7. Rear RH door (w/o door closer): INSPECT DOOR UNLOCK DETECTION SWITCH CON-**TINUITY**


Switch position	Tester connection	Specified condition
OFF (Door Lock set to LOCK)	-	No continuity
ON (Door Lock set to UNLOCK)	3 – 4	Continuity

If continuity is not as specified, replace the switch.

8. Driver's door (w/o door closer): **INSPECT DOOR LOCK MOTOR OPERATION**

- Connect the positive (+) lead from the battery to terminal 6 and the negative (-) lead to terminal 5, and check that the door lock link moves to UNLOCK position.
- Reverse the polarity and check that the door lock link (b) moves to LOCK position.


If operation is not as specified, replace the door lock assembly.



9. Passenger's door (w/o door closer) : INSPECT DOOR LOCK MOTOR OPERATION

- (a) Connect the positive (+) lead from the battery to terminal 2 and the negative (-) lead to terminal 1, and check that the door lock link moves to UNLOCK position.
- (b) Reverse the polarity and check that the door lock link moves to LOCK position.


If operation is not as specified, replace the door lock assembly.



10. Rear LH door (w/o door closer) : INSPECT DOOR LOCK MOTOR OPERATION

- (a) Connect the positive (+) lead from the battery to terminal 4 and the negative (-) lead to terminal 3, and check that the door lock link moves to UNLOCK position.
- (b) Reverse the polarity and check that the door lock link moves to LOCK position.


If operation is not as specified, replace the door lock assembly.



11. Driver's door (w/ door closer) : INSPECT DOOR KEY LOCK AND UNLOCK SWITCH CONTINUITY

Switch position	Tester connection	Specified condition
LOCK	10 – 21	Continuity
OFF	-	No continuity
UNLOCK	9 – 21	Continuity


If continuity is not as specified, replace the switch.



12. Driver's door (w/ door closer): INSPECT DOOR UNLOCK DETECTION SWITCH CONTINUITY

Switch position	Tester connection	Specified condition
OFF (Door Lock set to LOCK)	-	No continuity
ON (Door Lock set to UNLOCK)	7 – 20	Continuity


If continuity is not as specified, replace the switch.



13. Passenger's door (w/ door closer) : INSPECT DOOR UNLOCK DETECTION SWITCH CONTINUITY

Switch position	Tester connection	Specified condition
OFF (Door Lock set to LOCK)	-	No continuity
ON (Door Lock set to UNLOCK)	3 – 4	Continuity


If continuity is not as specified, replace the switch.



14. Rear LH door (w/ door closer) : INSPECT DOOR UNLOCK DETECTION SWITCH CONTINUITY

Switch position	Tester connection	Specified condition
OFF (Door Lock set to LOCK)	-	No continuity
ON (Door Lock set to UNLOCK)	7 – 20	Continuity


If continuity is not as specified, replace the switch.



15. Rear RH door (w/ door closer) : INSPECT DOOR UNLOCK DETECTION SWITCH CONTINUITY

Switch position	Tester connection	Specified condition
OFF (Door Lock set to LOCK)	-	No continuity
ON (Door Lock set to UNLOCK)	7 – 20	Continuity


If continuity is not as specified, replace the switch.



16. Front door (w/ door closer) : INSPECT DOOR LOCK MOTOR OPERATION

- (a) Connect the positive (+) lead from the battery to terminal 2 and the negative (-) lead to terminal 1, and check that the door lock link moves to UNLOCK position.
- (b) Reverse the polarity and check that the door lock link moves to LOCK position.


If operation is not as specified, replace the door lock assembly.



17. Rear door (w/ door closer) : INSPECT DOOR LOCK MOTOR OPERATION

- (a) Connect the positive (+) lead from the battery to terminal 2 and the negative (-) lead to terminal 1, and check that the door lock link moves to UNLOCK position.
- (b) Reverse the polarity and check that the door lock link moves to LOCK position.

If operation is not as specified, replace the door lock assembly.



18. INSPECT LUGGAGE COMPARTMENT DOOR OPEN-ER MAIN SWITCH CONTINUTY

Switch position	Tester connection	Specified condition
OFF (Push)	-	No continuity
ON (Push and turn)	1 – 2	Continuity

If continuity is not as specified, replace the switch.

19. INSPECT LUGGAGE COMPARTMENT DOOR OPEN-ER MAIN SWITCH CONTINUTY

Switch position	Tester connection	Specified condition
OFF	2 – B	Continuity
ON (Pull)	1 – L 2 – B	Continuity

If continuity is not as specified, replace the switch.

20. INSPECT LUGGAGE COMPARTMENT DOOR OPEN-ER SWITCH AND MAIN SWITCH CIRCUIT

(See page DI-1135)